

Traffic Impact Assessment

Perdaman Urea Project

CW1055600



Prepared for
Perdaman Chemicals and Fertilisers Pty Ltd

28 August 2019

Contact Information

Cardno (WA) Pty Ltd

ABN 77 009 119 000

11 Harvest Terrace
West Perth WA 6005
Australia

www.cardno.com

Phone +61 8 9273 3888

Fax +61 8 9486 8664

Document Information

Prepared for	Perdaman Chemicals and Fertilisers Pty Ltd
Project Name	Perdaman Urea Project
File Reference	CW1055600-TR-RP-001-A_Perdaman_Chemicals_and_Fertilisers_TIA_V2SLA.docx
Job Reference	CW1055600
Date	28 August 2019
Version Number	A

Author(s):

Sedrik Aralar/Edmond Hoang
Traffic Engineer

Effective Date 28/08/2019

Approved By:

Ray Cook
Manager – Traffic and Transport Planning

Date Approved 28/08/2019

Document History

Version	Effective Date	Description of Revision	Prepared by	Reviewed by
A	23/08/2019	For Issue	SA/EH	SL

© Cardno. Copyright in the whole and every part of this document belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or in or on any media to any person other than by agreement with Cardno.

This document is produced by Cardno solely for the benefit and use by the client in accordance with the terms of the engagement. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by any third party on the content of this document.

Our report is based on information made available by the client. The validity and comprehensiveness of supplied information has not been independently verified and, for the purposes of this report, it is assumed that the information provided to Cardno is both complete and accurate. Whilst, to the best of our knowledge, the information contained in this report is accurate at the date of issue, changes may occur to the site conditions, the site context or the applicable planning framework. This report should not be used after any such changes without consulting the provider of the report or a suitably qualified person.

FOREWORD

CLARIFICATION OF PROJECT AREA

Some technical reports, including this one, were completed in the early planning and design phases of the Project. As such, some of the maps / and aerial views depict the following anomalies associated with the actual Project area:

- i. The Project boundary of Site F does not have an extension from the south west corner.
- ii. The southern alignment of Hearson Cove Road is not applicable. Only the alignment on the north side of Site F will apply to the Project.
- iii. The footprint of the port area is limited to the area depicting the *Storage Shed – Port* and *Shiploader – Feed Conveyor*. It does not extend out along the Bulk Liquids Berth Jetty.

Figures A and B below provides further clarification of this discrepancy.




Figure A: Incorrect / superseded Project Area.




Figure B: Correct Project Area.

Table of Contents

1	Introduction	1
	1.1 Background	1
	1.2 Site Location	1
	1.3 Land Use	2
2	Existing Situation	3
	2.1 Existing Road Network	3
	2.2 Existing Intersections	4
	2.3 Existing Traffic Volumes	6
	2.4 Crash assessment	6
3	Proposed Development	9
	3.1 Development Overview	9
	3.2 Access Arrangements	10
	3.3 Car Parking Provision	11
4	Changes to Surrounding Transport Network	12
	4.1 Road Network	12
	4.2 Intersection Controls	12
5	Analysis of Transport Network	13
	5.1 Assessment Years and Time Period	13
	5.2 Traffic Generation	13
	5.3 Traffic Volumes	15
	5.4 Key Assumptions	20
	5.5 Intersection Performance	21
6	Summary	30

Appendices

Appendix A WAPC Checklist for TIA

Appendix B Site Plans

Tables

Table 2-1	Existing Road Network	3
Table 2-2	Traffic Volumes	6
Table 2-3	Hearson Cove Road Midblock Crash Data (entire length)	7
Table 2-4	Burrup Road Midblock Crash Data (From Dampier Highway to Village Road)	7
Table 2-5	King Bay Road – Mof Road Intersection Crash Data	8
Table 2-6	Burrup Road – Hearson Cove Road Intersection Crash Data	8
Table 2-7	Burrup Road – Village Road Intersection Crash Data	8
Table 5-1	Summary of Assessment Scenarios and Intersections	13
Table 5-2	Directional Distribution	15
Table 5-3	Total Trip Generation – Peak Hours	15
Table 5-4	Burrup Road/Hearson Cove Road Intersection Operation – Scenario 1	21
Table 5-5	Burrup Road/Dampier Highway Intersection Operation – Scenario 1	22
Table 5-6	Burrup Road/Access 2 Intersection Operation – Scenario 2	23
Table 5-7	Burrup Road/Hearson Cove Road Intersection Operation – Scenario 2	24
Table 5-8	Burrup Road/Dampier Highway Intersection Operation – Scenario 2	25
Table 5-9	Burrup Road/Hearson Cove Road Intersection Operation – Scenario 3	26
Table 5-10	Burrup Road/Dampier Highway Intersection Operation – Scenario 3	26
Table 5-11	Burrup Road/Hearson Cove Road Intersection Operation – Scenario 4	27
Table 5-12	Burrup Road/Dampier Highway Intersection Operation – Scenario 4	27
Table 5-13	Burrup Road/Dampier Highway Intersection Operation – Scenario 4 (with increased signal frequency for Burrup Road right turn)	28

Figures

Figure 1-1	Site Location	1
Figure 1-2	Zoning Map	2
Figure 2-1	Road Network Classification	3
Figure 2-2	RAV Network	4
Figure 2-3	Burru Road/Hearson Cove Road Intersection	5
Figure 2-4	Burru Road/King Bay Road Intersection	5
Figure 2-5	Burru Road/Dampier Highway Intersection	6
Figure 2-6	Crash Locations and Severity	7
Figure 3-1	Indicative Infrastructure	9
Figure 3-2	Project Timeline	10
Figure 3-3	Site Accesses	11
Figure 4-1	Proposed Realignment of Hearson Cove Road	12
Figure 5-1	Scenario 1 – 2019 Existing traffic without development traffic	16
Figure 5-2	Scenario 2 – 2021 Traffic with construction development traffic	17
Figure 5-3	Scenario 3 – 2024 Traffic with operational development traffic	18
Figure 5-4	Scenario 4 – 2034 Traffic with operational development traffic	19
Figure 5-5	SIDRA Layout for Burru Road/Hearson Cove Road Intersection (Existing)	21
Figure 5-6	SIDRA Layout for Burru Road/Dampier Highway Intersection	22
Figure 5-7	SIDRA Layout for Burru Road/Access 2 Intersection (with CHR)	23
Figure 5-8	SIDRA Layout for Burru Road/Hearson Cove Road Intersection (modified)	24
Figure 5-9	Intersection Warrants	29

1 Introduction


1.1 Background

Cardno has been commissioned by Perdaman Chemical and Fertilisers Pty Ltd (The Client) to prepare a Traffic Impact Assessment (TIA) for the proposed industrial development in Murujuga (also known as the Burrup Peninsula). The report aims to outline in detail the traffic impacts of the development to the surrounding road network during its construction and operation phases.

1.2 Site Location

The development is called the Perdaman Urea Project, also known as Project Destiny (The Project), which is located in the proposed Burrup Strategic Industrial Area (BSIA) at Murujuga as shown in **Figure 1-1**. Specifically, the TIA focuses on Sites C and F of this project. The two Sites are located in vacant land approximately 8 km from Dampier and 20 km north-west of Karratha on the north-west coastline of Western Australia.

Figure 1-1 Site Location




Source: Environmental Review Document

1.3 Land Use

As shown in **Figure 1-2**, the Sites are currently zoned under “Strategic Industry” according to the City of Karratha Local Planning Scheme.

Figure 1-2 Zoning Map



Source: City of Karratha Local Planning Scheme

1.3.2 Surrounding Land Uses


Nearby land uses comprise of other industrial facilities. Dampier is located approximately 8km southwest and Karratha is located approximately 20km southeast.

2 Existing Situation

2.1 Existing Road Network

The layout and classification of the roads under the *Main Roads WA Road Hierarchy* surrounding the two Sites are presented in **Figure 2-1**.

Figure 2-1 Road Network Classification



Source: MRWA Road Information Mapping System

The characteristics of the existing surrounding road network are described in **Table 2-1**.

Table 2-1 Existing Road Network

Road Name	Road Network					
	Road Hierarchy	Jurisdiction	No. of Lanes	No. of Footpaths	Width (m)	Posted Speed Limit (km/h)
Burrup Road	Primary Distributor	MRWA	2	0	7-11	80/100
Hearson Cove Road	Access Road	Local Govt.	2	0	7	60
King Bay Road	Access Road	Local Govt.	2	0	7.5	60
Mof Road	Access Road	Local Govt.	2	0	7.2	60

Source: MRWA Road Information Mapping System; Nearmap

Burrup Road is a primary distributor connecting the industrial areas of Burrup to Dampier Highway, while Hearson Cove Road is an access road leading to Hearson’s Cove. King Bay Road and Mof Road are access roads connecting jetties and industrial areas to Burrup Road.

2.1.2 RAV Network

Figure 2-2 shows the RAV network within the surrounding area of the Site. Burrup Road is classified as part of the RAV Network 10.

Figure 2-2 RAV Network



Source: Main Roads WA

2.2 Existing Intersections

Burrup Road/Hearson Cove Road intersection is located west of the Site and is a give-way controlled T-intersection, with priority given to Burrup Road (Figure 2-3).

Figure 2-3 Burrup Road/Hearson Cove Road Intersection



Source: Nearmap

Burrup Road/King Bay Road intersection is located north of the Site and is a give-way controlled T-intersection, with priority given to Burrup Road (Figure 2-4).

Figure 2-4 Burrup Road/King Bay Road Intersection



Source: Nearmap

Burrup Road/Dampier Highway Road intersection is located south of the Site and is a signal controlled T-intersection (**Figure 2-5**).

Figure 2-5 Burrup Road/Dampier Highway Intersection



Source: Nearmap

2.3 Existing Traffic Volumes

Existing traffic volumes near the Site were sourced from Main Roads Traffic Map and are shown in **Table 2-2**.

Table 2-2 Traffic Volumes

Location	Year	Average Daily Traffic (%HV)
Burrup Road (North of Hearson Cove Road)	2017/18	2,600 (16.0%)
Burrup Road (North of Village Road)	2015/16	1,413 (19.4%)

Source: MRWA Traffic Map


2.4 Crash assessment

Crash data were obtained from the Main Roads Crash Reporting Centre. The search covered all recorded traffic accidents within 5 kilometres from the site, between 1 January 2014 and 31 December 2018, for the following roads:

- > Burrup Road
- > Hearson Cove Road
- > King Bay Road

Figure 2-6 shows the locations and severity of recorded crashes near the Site, where red areas are locations where accidents occur more often. Table 2-3 to Table 2-7 shows the breakdown of each crash categorised in terms of crash type and severity.

Figure 2-6 Crash Locations and Severity



Source: MRWA Crash Reporting Centre

Table 2-3 Hearson Cove Road Midblock Crash Data (entire length)

Type of Crash (RUM Code)	Fatal	Hospital	Medical	Major Property Damage	Minor Property Damage	Total Crashes
Hit Object	1	-	1	-	-	2
Total	1	0	1	0	0	2

Table 2-4 Burrup Road Midblock Crash Data (From Dampier Highway to Village Road)

Type of Crash (RUM Code)	Fatal	Hospital	Medical	Major Property Damage	Minor Property Damage	Total Crashes
Hit Object	-	-	-	2	-	2
Unspecified	-	-	-	2	-	2
Right Angle	-	-	-	1	-	1
Total	0	0	0	5	0	5

Table 2-5 King Bay Road – Mof Road Intersection Crash Data

Type of Crash (RUM Code)	Fatal	Hospital	Medical	Major Property Damage	Minor Property Damage	Total Crashes
Non Collision	-	-	-	1	-	1
Rear End	-	-	-	1	-	1
Total	0	0	0	2	0	2

Table 2-6 Burrup Road – Hearson Cove Road Intersection Crash Data

Type of Crash (RUM Code)	Fatal	Hospital	Medical	Major Property Damage	Minor Property Damage	Total Crashes
Rear End	-	-	-	1	-	1
Non Collision	-	1	-	-	-	1
Total	0	1	0	1	0	2

Table 2-7 Burrup Road – Village Road Intersection Crash Data

Type of Crash (RUM Code)	Fatal	Hospital	Medical	Major Property Damage	Minor Property Damage	Total Crashes
Right Turn Thru	-	-	-	1	-	1
Total	0	0	0	1	0	1

Source: MRWA Crash Reporting Centre

A review of the crash data shows:


- > One fatal crash was recorded along Hearson Cove Road caused by an out of control vehicle hitting an object;
- > One crash requiring hospitalization were recorded;
- > The most common crash type is Hit Object with 4 recorded incidents; and
- > The most common crash severity is Major Property Damage with 9 recorded incidents.

3 Proposed Development

3.1 Development Overview

The proposed development consists of a chemical and fertiliser production plant. The main plant infrastructure/equipment is located in Site C and administrative buildings are located in Site F. The proposed development concept shown in **Figure 3-1**.

Figure 3-1 Indicative Infrastructure



Source: Perdaman

The development concept layout plan is included in **Appendix A**.

3.1.1 Project Timeline

The project timeline for Project Destiny is shown in **Figure 3-2**.

Figure 3-2 Project Timeline

PROJECT TIMELINE	
Public announcement of project	October 2018
Commencing community consultation	February 2019
Permitting and environment approvals	December 2019 – March 2020
Engineering	October 2018
Construction contract arrangements finalised	June 2019
Financial close	2nd quarter 2020
Field construction start	2nd quarter 2020
Mechanical completion	4th quarter 2023
Startup begins	1st quarter 2024
Full production	2nd quarter 2024


Source: Perdaman Chemical and Fertilisers

3.2 Access Arrangements

The proposed access arrangements for the Site are shown in **Figure 3-3**. These include:

- > Access 1 and 2 provide access to Site C off Burrup Road. These two access connections will provide access to Site C during different phases of construction and also provide movement between Sites C & F, until the Causeway is established. During operations, Access 2 will be the primary access point into the plant area (mostly for trucks) and include a gatehouse. Traffic volumes at both of these accesses are expected to be very low.
- > Access 3 and 4 provide access to Site F off the realigned Hearson Cove Road. Construction traffic and material deliveries will access the Site primarily via these two accesses and into the proposed laydown area. Vehicles, plant and machinery will then move across the Causeway to access Site C once constructed, prior to this there will be a short period where construction traffic will travel between Site C and F using the Burrup Road and after the Causeway is constructed only light vehicles and bus traffic will enter and exit the site via the southern entrance on Site C.
- > A causeway connecting Site C and Site F.
- > The existing intersection of Burrup Road / Hearson Cove Road will be closed once the Hearson Cove Road realignment has been completed. It is recommended that all access to Site F be from the new alignment of Hearson Cove Road once operational.

Figure 3-3 Site Accesses



3.3 Car Parking Provision

According to the *City of Karratha Town Planning Scheme No.8*, car parking requirements for an industrial facility is at the council's discretion. During day-to-day operations, approximately 200 people will be employed and the proposed parking provision will need to accommodate these employees as well as visitors.

4 Changes to Surrounding Transport Network


4.1 Road Network

4.1.1 Hearson Cove Road Realignment

The realignment of Hearson Cove Road will include shifting part of the road to the north to improve the road alignment as well as improving accessibility for heavy vehicles. **Figure 4-1** shows the proposed changes to the road.

The road realignment will be completed prior to the commencement of construction works for Site C and F.

Figure 4-1 Proposed Realignment of Hearson Cove Road



Source: Landcorp

4.2 Intersection Controls

As part of the proposed realignment of Hearson Cove Road, the Burrup Road/Hearson Cove Road intersection will also be upgraded as shown in **Figure 4-1** above. The proposed upgrades include turning pockets for the left and right turn movements into Hearson Cove Road as well as acceleration lanes for movements out onto Burrup Road.

5 Analysis of Transport Network

5.1 Assessment Years and Time Period

5.1.1 Key Intersections

A detailed traffic analysis has been undertaken at the following key intersections:

- > Burrup Road/Dampier Highway
- > Burrup Road/Hearson Cove Road
- > Burrup Road/Access 2 (during construction phase only, Scenario 2)

Access 1, 3 and 4 have not been assessed as the anticipated traffic volumes at these access points are considered to be low and the associated traffic impacts are considered to be negligible.

5.1.2 Assessment Years

The following scenarios have been assessed:

- > Scenario 1 – 2019 Existing traffic without development traffic
- > Scenario 2 – 2021 Traffic with construction development traffic
- > Scenario 3 – 2024 Traffic with operational development traffic
- > Scenario 4 – 2034 Traffic with operational development traffic

Each scenario has been assessed for the Weekday AM (6:00am to 7:00am) and Weekday PM (5:00pm to 6:00pm) Peak Periods as per the requirements of the WAPC *Transport Assessment Guidelines*.

Background traffic growth forecasts are not available, therefore a conservative linear growth rate of 2% per annum has been used to estimate increases in background traffic flows for Scenarios 2, 3 and 4.

Table 5-1 provides a summary of which intersections will be assess for each scenario.

Table 5-1 Summary of Assessment Scenarios and Intersections

	Burrup Road/Hearson Cove Road	Burrup Road/Access 2	Burrup Road/Dampier Highway
Scenario 1	✓	✗	✓
Scenario 2	✓	✓	✓
Scenario 3	✓	✗	✓
Scenario 4	✓	✗	✓

5.2 Traffic Generation

The peak traffic generation for the proposed Site is likely to vary depending on the various stages during development. The peak trip generation periods will generally occur at the following stages:

- > The construction phase – this stage generally involves an influx of traffic from construction workers, truck deliveries and materials transportation. Approximately, 1,500 construction staff are expected at the peak of the construction phase.
- > The operation phase – this refers to day-to-day operations when the Site is completed and fully operational. The traffic generated primarily comprises Site employees with an estimated 200 employees living and working within the region.

The process used to derive the trip generation during the construction and operational phase are detailed in the sections below.

5.2.1 Construction Phase Trip Generation

The trip generation for the construction phase is made up of two components; earthworks truck trips and construction staff trips. The following information and assumptions have been determined in regards to earthworks truck trips

- > The estimated earthworks volumes (to be transported to and from the Site) have been provided by the Client which will be used to estimate truck traffic volumes. Approximately, 1,200,000 m³ of earthwork material will be transported to and from the construction sites.
- > To convert volume into weight, the density of the earthwork material needs to be known. Therefore, it is assumed that the majority of earthworks material consists of dry soil clay which has a density of 2,000 kg/m³.
- > The total weight of the earthworks material is given by the following equation, Weight = Volume x Density. Approximate 2,400,000 tonnes of earthworks material will be transported to and from the Site during the construction period.
- > The bulk earthworks period is estimated to be 5 months. Excluding weekends, this equates to approximately 110 construction days.
- > The construction peak is assumed to be during 2021.
- > It is assumed that the class of trucks used for materials transport will be B-triples, which have an average payload of 53 tonnes.
- > It is assumed that, in a worst-case scenario, 30% of these trucks will arrive/depart during the morning and afternoon peak periods.

Based on the above assumptions, the estimated traffic volumes for construction trucks during the peak period is 124 vph.

The information and assumptions for construction staff trips are as follows:

- > The maximum number of construction staff on-site is approximately 1,425 workers. (1,500 construction workers in total with 5% working at the port).
- > All workers will travel to and from the Site via private bus service. A bus service arrives on site in the morning peak to drop off workers and picking them up in the afternoon peak.
- > The estimated bus capacity is 56 passengers.
- > Only senior staff will likely travel by car which comprises of approximately 20 vehicle trips.

Based on the above assumptions, the anticipated traffic volumes for operational staff during the peak period is 45 vph. Overall, the peak period trip generation during the construction period is 169 vph.

5.2.2 Operational Phase Trip Generation

The following information and assumptions have been determined in regards to trip generation when the Site is operational:

- > Employee shifts comprise of 12 hour shifts. During the AM peak hour, day shift workers will arrive on Site while the night shift workers leave the Site and vice versa.
- > Private vehicle mode share is conservatively assumed to be 100%, i.e. it is assumed that all employees will drive to and from the Site, with no ride-sharing or car-pooling.
- > The products produced by the Site will be transported to Dampier Port via a conveyor system. As a result, heavy vehicles traveling to and from the Site during day-to-day operation is expected to be low. Therefore, the heavy vehicle percentage is assumed to be 5% to account for delivery, maintenance and other trucks traveling to and from the Site.

Based on the above assumptions, the anticipated traffic volumes for construction staff during the peak period is 200 vph.

5.2.3 Trip Distribution

The inbound and outbound trip distribution for during the construction phase is based on the *Institute of Transportation Engineers (ITE) "Trip Generation" 10th Edition* which is shown in **Table 5-2**.

Table 5-2 Directional Distribution

Land Use	Weekday AM Peak		Weekday PM Peak	
	In	Out	In	Out
Industrial	87%	13%	21%	79%

All Site traffic arriving/departing from the Site will be traveling from the south of Burrup Road which lead to key areas such as Dampier and Karratha. It is unlikely that any development traffic will travel north as it only leads to other industrial sites.

5.2.4 Total Trip Generation

The total two-way trip generation for the proposed development is summarised in **Table 5-3**.

Table 5-3 Total Trip Generation – Peak Hours

Peak Period	Weekday AM Peak	Weekday PM Peak
Construction Peak	169	169
Operation Peak	200	200

5.3 Traffic Volumes

Figure 5-1 through to **Figure 5-4** shows the traffic volumes for each scenario. Background traffic volumes comprised of data obtained from various sources which include Main Roads Traffic Map, SCATS and Hearson Cove Foreshore Management Plan.

Figure 5-1 Scenario 1 – 2019 Existing traffic without development traffic




Figure 5-2 Scenario 2 – 2021 Traffic with construction development traffic




Figure 5-3 Scenario 3 – 2024 Traffic with operational development traffic





Figure 5-4 Scenario 4 – 2034 Traffic with operational development traffic



5.4 Key Assumptions

The key traffic assumptions for this development are as follows:

5.4.1 General Assumptions

- > The anticipated opening year of the development is 2024 as per the project timeline
- > It is assumed that the construction peak period will likely occur during 2021.
- > Morning and afternoon peak periods are based on the current traffic volumes from Main Roads Traffic Map which are 6:00am to 7:00am and 5:00pm to 6:00pm respectively.
- > Heavy vehicle volumes are based on Main Roads WA Traffic Map.

5.4.2 Trip Generation, Distribution and Assignment

The trip generation, distribution and assignment assumptions are provided in **Section 5.2**.

5.4.3 SIDRA Assumptions

- > Vehicle user classes have been set up based on Main Roads WA Operational Modelling Guidelines.
- > The geometry for Burrup Road/Hearson Cove Road intersection in Scenarios 2-4 is based on the modified layout from the proposed realignment of Hearson Cove Road as shown in **Figure 4-1**.
- > Signal phasing and timing for Burrup Road/Dampier Highway is based on the SCATS data obtained from Main Roads WA.

5.5 Intersection Performance

5.5.1 Scenario 1 – 2019 Existing traffic without development traffic

5.5.1.1 Burrup Road/Hearson Cove Road

The following presents the Burrup Road/Hearson Cove Road intersection results for Scenario 1. **Figure 5-5** is a SIDRA layout representation of the intersection and **Table 5-4** shows the results of the analysis.

Figure 5-5 SIDRA Layout for Burrup Road/Hearson Cove Road Intersection (Existing)




Table 5-4 Burrup Road/Hearson Cove Road Intersection Operation – Scenario 1

Intersection Approach	Scenario 1 (AM)				Scenario 1 (PM)				
	DOS	Delay (s)	LOS	95% Queue (m)	DOS	Delay (s)	LOS	95% Queue (m)	
Burrup Rd (S)	T	0.22	0	A	0	0.053	0	A	0
	R	0.017	7.1	A	0.5	0.02	7.8	A	0.6
Hearson Cove Rd (E)	L	0.018	5.7	A	0.5	0.022	6.4	A	0.6
	R	0.002	8.6	A	0	0.001	7.9	A	0
Burrup Rd (N)	L	0.04	6.9	A	0	0.163	7	A	0
	T	0.04	0	A	0	0.163	0	A	0

5.5.1.2 Burrup Road/Dampier Highway

The following presents the Burrup Road/Dampier Highway intersection results for Scenario 1. **Figure 5-6** is a SIDRA layout representation of the intersection and **Table 5-5** shows the results of the analysis.

Figure 5-6 SIDRA Layout for Burrup Road/Dampier Highway Intersection




Table 5-5 Burrup Road/Dampier Highway Intersection Operation – Scenario 1

Intersection Approach	Scenario 1 (AM)				Scenario 1 (PM)				
	DOS	Delay (s)	LOS	95% Queue (m)	DOS	Delay (s)	LOS	95% Queue (m)	
Dampier Hwy (SE)	T	0.099	0	A	0	0.131	0	A	0
	R	0.193	10.3	B	29.1	0.082	15	B	9.6
Burrup Rd (N)	L	0.038	9.6	A	4.8	0.147	12.9	B	17.4
	R	0.331	80.7	F	2.4	0.246	44.9	D	6.1
Dampier Hwy (NW)	L	0.007	9.1	A	0.2	0.004	9.2	A	0.1
	T	0.255	47.5	D	21.3	0.262	23.9	C	22.9

5.5.2 Scenario 2 – 2021 Traffic with construction development traffic

5.5.2.1 Burrup Road/Access 2

The following presents the Burrup Road/Access 2 intersection results for Scenario 2. **Figure 5-7** is a SIDRA layout representation of the intersection and **Table 5-6** shows the results of the analysis.

Figure 5-7 SIDRA Layout for Burrup Road/Access 2 Intersection (with CHR)




Table 5-6 Burrup Road/Access 2 Intersection Operation – Scenario 2

Intersection Approach	Scenario 2 (AM)				Scenario 2 (PM)				
	DOS	Delay (s)	LOS	95% Queue (m)	DOS	Delay (s)	LOS	95% Queue (m)	
Burrup Rd (S)	T	0.116	0	A	0	0.028	0	A	0
	R	0.126	9.9	A	23.9	0.055	16.1	C	8.8
Access 2 (E)	L	0.029	8.4	A	3.8	0.289	19.8	C	47
	R	0.029	11.6	B	3.8	0.289	10.7	B	47
Burrup Rd (N)	L	0.043	6.9	A	0	0.173	7	A	0
	T	0.043	0	A	0	0.173	0	A	0

5.5.2.2 Burrup Road/Hearson Cove Road

The following presents the Burrup Road/Hearson Cove Road intersection results for Scenario 2. **Figure 5-8** is a SIDRA layout representation of the modified intersection and **Table 5-7** shows the results of the analysis.

Figure 5-8 SIDRA Layout for Burrup Road/Hearson Cove Road Intersection (modified)




Table 5-7 Burrup Road/Hearson Cove Road Intersection Operation – Scenario 2

Intersection Approach	Scenario 2 (AM)				Scenario 2 (PM)				
	DOS	Delay (s)	LOS	95% Queue (m)	DOS	Delay (s)	LOS	95% Queue (m)	
Burrup Rd (S)	T	0.283	0	A	0	0.068	0	A	0
	R	0.108	8.5	A	6.2	0.058	11.3	B	3
Hearson Cove Rd (E)	L	0.031	6.2	A	0	0.094	6.2	A	0
	R	0.003	12.4	B	0.1	0.002	9.9	A	0
Burrup Rd (N)	L	0.001	6.9	A	0	0.001	6.9	A	0
	T	0.05	0	A	0	0.217	0	A	0

5.5.2.3 Burrup Road/Dampier Highway

The following presents the Burrup Road/Dampier Highway intersection results for Scenario 2. **Table 5-8** shows the results of the analysis.

Table 5-8 Burrup Road/Dampier Highway Intersection Operation – Scenario 2

Intersection Approach	Scenario 2 (AM)				Scenario 2 (PM)				
	DOS	Delay (s)	LOS	95% Queue (m)	DOS	Delay (s)	LOS	95% Queue (m)	
Dampier Hwy (SE)	T	0.103	0	A	0	0.136	0	A	0
	R	0.28	10.6	B	46	0.104	15.1	B	12.3
Burrup Rd (N)	L	0.045	9.6	A	5.9	0.227	13.2	B	28.4
	R	0.414	81.2	F	3	0.388	45.6	D	9.8
Dampier Hwy (NW)	L	0.013	9.2	A	0.3	0.005	9.2	A	0.1
	T	0.265	47.6	D	22.1	0.273	23.9	C	23.9

5.5.3 Scenario 3 – 2024 Traffic with operational development traffic

5.5.3.1 Burrup Road/Hearson Cove Road

The following presents the Burrup Road/Hearson Cove Road intersection results for Scenario 3. **Table 5-9** shows the results of the analysis.

Table 5-9 Burrup Road/Hearson Cove Road Intersection Operation – Scenario 3

Intersection Approach	Scenario 3 (AM)				Scenario 3 (PM)				
	DOS	Delay (s)	LOS	95% Queue (m)	DOS	Delay (s)	LOS	95% Queue (m)	
Burrup Rd (S)	T	0.257	0	A	0	0.06	0	A	0
	R	0.101	7.4	A	3.1	0.13	8.6	A	3.9
Hearson Cove Rd (E)	L	0.074	5.7	A	0	0.074	5.7	A	0
	R	0.002	11.5	B	0.1	0.002	9.9	A	0
Burrup Rd (N)	L	0.001	6.9	A	0	0.001	6.9	A	0
	T	0.045	0	A	0	0.182	0	A	0

5.5.3.2 Burrup Road/Dampier Highway

The following presents the Burrup Road/Dampier Highway intersection results for Scenario 3. **Table 5-10** shows the results of the analysis.

Table 5-10 Burrup Road/Dampier Highway Intersection Operation – Scenario 3

Intersection Approach	Scenario 3 (AM)				Scenario 3 (PM)				
	DOS	Delay (s)	LOS	95% Queue (m)	DOS	Delay (s)	LOS	95% Queue (m)	
Dampier Hwy (SE)	T	0.109	0	A	0	0.144	0	A	0
	R	0.264	10.5	B	42.7	0.163	15.4	B	20
Burrup Rd (N)	L	0.083	9.7	A	11	0.214	13.2	B	26.5
	R	0.827	84.6	F	6.3	0.363	45.5	D	9.1
Dampier Hwy (NW)	L	0.012	9.2	A	0.2	0.008	9.2	A	0.2
	T	0.279	47.7	D	23.4	0.287	24	C	25.3

5.5.4 Scenario 4 – 2034 Traffic with operational development traffic

5.5.4.1 Burrup Road/Hearson Cove Road

The following presents the Burrup Road/Hearson Cove Road intersection results for Scenario 4. **Table 5-11** shows the results of the analysis.

Table 5-11 Burrup Road/Hearson Cove Road Intersection Operation – Scenario 4

Intersection Approach	Scenario 4 (AM)				Scenario 4 (PM)				
	DOS	Delay (s)	LOS	95% Queue (m)	DOS	Delay (s)	LOS	95% Queue (m)	
Burrup Rd (S)	T	0.291	0	A	0	0.071	0	A	0
	R	0.106	7.4	A	3.3	0.146	9	A	4.3
Hearson Cove Rd (E)	L	0.077	5.7	A	0	0.077	5.7	A	0
	R	0.003	12.8	B	0.1	0.002	11	B	0.1
Burrup Rd (N)	L	0.001	6.9	A	0	0.001	6.9	A	0
	T	0.053	0	A	0	0.215	0	A	0

5.5.4.2 Burrup Road/Dampier Highway

The following presents the Burrup Road/Dampier Highway intersection results for Scenario 4. **Table 5-12** shows the results of the analysis.

Table 5-12 Burrup Road/Dampier Highway Intersection Operation – Scenario 4

Intersection Approach	Scenario 4 (AM)				Scenario 4 (PM)				
	DOS	Delay (s)	LOS	95% Queue (m)	DOS	Delay (s)	LOS	95% Queue (m)	
Dampier Hwy (SE)	T	0.128	0	A	0	0.17	0	A	0
	R	0.303	10.6	B	50.8	0.179	15.4	B	22.2
Burrup Rd (N)	L	0.09	9.7	A	12.1	0.244	13.3	B	30.8
	R	0.827	84.6	F	6.3	0.414	45.7	D	10.5
Dampier Hwy (NW)	L	0.015	9.3	A	0.3	0.009	9.3	A	0.2
	T	0.331	48.1	D	28	0.34	24.4	C	30.4

5.5.5 Analysis Results Summary

A summary of the SIDRA results are as follows:

- > The SIDRA results for the Burrup Road/Access 2 intersection show it will operate at an acceptable level of service for all scenarios.
- > The SIDRA results for the Burrup Road/Hearson Cove Road intersection show it will operate at an acceptable level of service for all scenarios.
- > The SIDRA results for the Burrup Road/Dampier Highway intersection show it will operate at an acceptable level of service for all scenarios. The right turn movement from Burrup Road onto Dampier Highway shows LoS F during the AM peak for all scenarios, including existing (Scenario 1). However, this is considered to be satisfactory given that the volumes for the right turn are very low. As a result of the low traffic volumes, the signal frequency for this movement likely only triggers when a car approaches the right turn lane. Increasing the frequency of the phase that controls this movement will improve the LoS (as shown in **Table 5-13** for Scenario 4 which is the worst case) however, this is not necessary given the low right turn volumes and negligible queuing.


Table 5-13 Burrup Road/Dampier Highway Intersection Operation – Scenario 4 (with increased signal frequency for Burrup Road right turn)

Intersection Approach	Scenario 4 (AM)				
		DOS	Delay (s)	LOS	95% Queue (m)
Dampier Hwy (SE)	T	0.128	0	A	0
	R	0.345	15.6	B	80.1
Burrup Rd (N)	L	0.087	9.3	A	12.1
	R	0.094	66.8	E	5.3
Dampier Hwy (NW)	L	0.015	10.4	B	0.9
	T	0.377	56.7	E	32.4

5.5.6 Intersection Turn Warrant Assessment

As Access 1 and 2 are located along Burrup Road which is under the authority of Main Roads WA, a check against the warrants for turn pockets from the Main Roads WA *Supplement to Austroads Guide to Road Design - Part 4* was conducted. The results in **Figure 5-9** show that a channelised right turn treatment (CHR) and a basic left turn treatment (BAL) is required for these intersections. However, it is important to note that outside of the construction period, traffic volumes at Access 1 and 2 will be very low as the accesses will only be used on rare occasions by heavy vehicles.

Figure 5-9 Intersection Warrants



6 Summary

Construction traffic primarily comprise of bulk material transport to and from the Site by large trucks (up to B-Triple). During construction, the majority of trucks will arrive on Site via the accesses on Burrup Road. The completion of the Causeway between Site C and F will also minimise the impacts at this access as alternate access arrangements are available. Construction workers will be transported to and from the Site via a shuttle bus service thereby significantly reducing the number of private vehicle trips.

During the operational phase, approximately 200 people will be employed and residing within the region. The traffic generated during this phase is slightly higher compared to the operational phase but the resulting traffic impacts remained relatively unchanged.

The main road linking to the Site is Burrup Road. All traffic to and from the Sites will be from the south of this road which leads to key areas such as Dampier and Karratha. Traffic from the north of Burrup Road is unlikely as the only developments further north are the ports and other industrial development.

The realignment of Hearson Cove Road and the relocation of the Burrup Road/Hearson Cove Road intersection will improve heavy vehicle accessibility and movement at this location.

As demonstrated in the Transport Impact Assessment (TIA), the overall traffic impacts on the existing road network during construction and day-to-day operations is considered to be minor and is unlikely to result in any capacity constraints.

The Transport Impact Assessment report has been prepared in accordance with the Western Australian Planning Commission (WAPC) *Transport Assessment Guidelines for Developments: Volume 4 – Individual Development*. The following conclusions have been made in regards to the proposed development:

- > The proposed development comprises of a chemical and fertiliser production plant facility.
- > The access arrangement for the Site include access off Burrup Road and Hearson Cove Road.
- > The traffic generated during the construction and operational peaks is 169 vph and 200 vph respectively.
- > The SIDRA results show that the intersections and accesses surrounding the Site operate at an acceptable level of service for all scenarios. The right turn movement from Burrup Road onto Dampier Highway shows LoS F during the AM peak for all scenarios, including existing (Scenario 1). However, this is considered to be satisfactory as the volumes are very low and queuing is negligible.
- > Overall, there is a relatively low volume of crashes within the surrounding area of the Site.

Perdaman Urea Project

APPENDIX

A

WAPC CHECKLIST FOR TIA

Item	Provided	Comments/Proposals
Summary		
Introduction/Background		
name of applicant and consultant	Included in Section 1	
development location and context	Included in Section 3	
brief description of development proposal	Included in Section 3	
key issues	N/A	
background information	Included in Section 1	
Existing situation		
existing site uses (if any)	Included in Section 1	
existing parking and demand (if appropriate)	N/A	
existing access arrangements	Included in Section 2	
existing site traffic	Included in Section 2	
surrounding land uses	Included in Section 1	
surrounding road network	Included in Section 2	
traffic management on frontage roads	Included in Section 2	
traffic flows on surrounding roads (usually am and pm peak hours)	Included in Section 2	
traffic flows at major intersections (usually am and pm peak hours)	Included in Section 2	
operation of surrounding intersections	Included in Section 5	
existing pedestrian/cycle networks	N/A	
existing public transport services surrounding the development	N/A	
Crash data	Included in Section 2	
Development proposal		
regional context	Included in Section 3	
proposed land uses	Included in Section 3	
table of land uses and quantities	Included in Section 3	
access arrangements	Included in Section 3	
parking provision	Included in Section 3	
end of trip facilities	N/A	
any specific issues	N/A	
road network	N/A	
intersection layouts and controls	N/A	

Item	Provided	Comments/Proposals
pedestrian/cycle networks and crossing facilities	N/A	
public transport services	N/A	
Integration with surrounding area	Included in Section 1	
surrounding major attractors/generators	Included in Section 1	
committed developments and transport proposals	N/A	
proposed changes to land uses within 1200 metres	N/A	
travel desire lines from development to these attractors/generators	Included in Section 5	
adequacy of existing transport networks	N/A	
deficiencies in existing transport networks	N/A	
remedial measures to address deficiencies	N/A	
Analysis of transport networks		
assessment years	Included in Section 5	
time periods	Included in Section 5	
development generated traffic	Included in Section 5	
distribution of generated traffic	Included in Section 5	
parking supply & demand	N/A	
base and "with development" traffic flows	Included in Section 5	
analysis of development accesses	Included in Section 5	
impact on surrounding roads	Included in Section 5	
impact on intersections	Included in Section 5	
impact on neighbouring areas	Included in Section 5	
road safety	Included in Section 2	
public transport access	N/A	
pedestrian access / amenity	N/A	
cycle access / amenity	N/A	
analysis of pedestrian / cycle networks	N/A	
safe walk/cycle to school (for residential and school site developments only)	N/A	
Traffic management plan (where appropriate)	N/A	

Perdaman Urea Project


APPENDIX

B

SITE PLANS




0000 GENERAL	0000 GENERAL		
1000 SYNGAS BLOCK	1100 REFORMING		
	1200 CO SHIFT		
	1300 CO2 REMOVAL SECTION		
	2400 CO2 COMPRESSION		
	2500 AMMONIA SYNTHESIS		
	2600 UREA SYNTHESIS	2610 TRAIN 1	
		2620 TRAIN 2	
		2700 UREA GRANULATION	2710 TRAIN 1
		2720 TRAIN 2	
	3100 PLANT & INSTRUMENT AIR	3110 FLANK AIR (BACK-UP)	
		3120 INSTRUMENT AIR (BACK-UP)	
	3200 E & I SYSTEMS	3210 POWER DISTRIBUTION SYSTEMS (LV AND MV)	
		3220 SUBSTATIONS	
		3230 EMERGENCY POWER (DIESEL GEN SETS)	
		3240 UPS	
		3250 PLANT LIGHTING	
		3260 DCS	
		3270 HES	
		3280 ANALYZER PACKAGES	
	3300 STEAM & CONDENSATE	3310 BWV CONDENSATE	
		3320 STEAM SYSTEMS	
	3400 FLARE	3410 AMMONIA FLARE	
		3420 SYNGAS FLARE	
		3430 TANK FLARE	
	3500 AIR SEPARATION UNIT	3510 AIR COMPRESSION	
		3520 SEPARATION	
		3530 LOR	
		3540 COMPRESSED AIR	
		3550 N2 COMPRESSION	
		3560 LIN	
	3600 POWER GENERATION	3610 GAS/ STEAM TURBINE	
		3620 HRSG	
		3630 STEAM TURBINE	
		3640 AUXILIARY BOLLER	
	3700 WATER TREATMENT PACKAGE	3710 DESALINATION	
		3720 POTABLE WATER	
		3730 DEMINERALISATION	
		3740 PROCESS WATER	
		3750 PROCESS CONDENSATE POLISHING	
	3800 SAFETY SYSTEMS	3810 FIRE DETECTION AND PROTECTION	
		3820 GAS DETECTION	
		3830 SAFETY SHOWER	
	3900 OTHER UTILITIES	3910 COOLING WATER- ONCE-THROUGH SEA WATER	
		3920 COOLING WATER- CLOSED LOOP	
		3930 FIRE WATER	
		3940 DRAINAGE (GFF/L)	
		3950 PONDS	
		3960 PROCESS WASTE WATER	
		3965 STORMWATER	
		3970 POTENTIALLY CONTAMINATED WATER	
		3975 OILY WATER	
		3980 SANITARY WASTE	
		3985 SOLID WASTE	
		3990 RETURN SALINE WATER PUMP STORAGE	
		3995 FUEL GAS	
	4100 UREA HANDLING	4110 PRODUCT CONVEYING- TO STORAGE	
		4120 PRODUCT STORAGE	
		4130 PRODUCT CONVEYING- TO PORT	
		4140 PRODUCT STORAGE- PORT	
		4150 PRODUCT SHIPLOADING	
	4200 STORAGE	4210 AMMONIA STORAGE TANK	
		4220 AMMONIA STORAGE TANK BOL-OFF UNIT	
		4230 DIESEL STORAGE	
		4240 LNG STORAGE	
		4250 HYDROGEN BULLET	
	4300 OSBL PIPERACKS		
	4400 BUILDINGS	4410 ENTRANCE GATE	
		4420 LABORATORY	
		4430 ADMINISTRATION	
		4440 MAINTENANCE	
		4450 ROADS	
		4460 WAREHOUSE	
		4470 CONTROL ROOM	
		4480 CHEMICAL STORAGE	



- PLANT COORDINATES N= 1,000 AND E= 1,000 WILL BE ESTABLISHED AT THE DATUM POINT FOR SITE 'F', AND WILL BE EQUIVALENT TO N= 7,718,238 AND E= 475,951 BASED ON DATUM GDA 94, MGA ZONE 50.
- REFERENCE PLANT ELEVATION 100,000 HPP (HIGH POINT PAVING) EQUALS 6,500 MASL (METERS ABOVE SEA LEVEL) ON SITES C AND F, ASSUMING A ROUGH GRADE ELEVATION OF 6,000 AND 10,000 MASL ON BOTH SITES.
- COORDINATES AND ELEVATIONS ARE EXPRESSED IN METERS; DIMENSIONS ARE EXPRESSED IN mm.
- ALL EQUIPMENT LOCATIONS AND SIZES SHOWN ARE PRELIMINARY AND WILL BE FINALIZED DURING DETAILED ENGINEERING.
- ROADS ARE 6 OR 8 METERS WIDE AND MAY BE OPTIMIZED BASED ON PROJECT NEEDS DURING DESIGN DEVELOPMENT.
- THE VERTICAL CLEARANCE FOR THE PIPE RACKS AT ALL ROAD CROSSINGS IS MINIMUM 5.5 METERS.
- THE COOLING WATER SUPPLY AND RETURN DISTRIBUTION HEADERS WILL RUN UNDERGROUND. THE SUPPLY AND RETURN COOLING WATER LINES TO/ FROM VARIOUS USERS WILL BRANCH FROM THE UNDERGROUND RUN OF COOLING WATER LINES IN UNITS AND WILL THEN RUN ABOVEGROUND.

- HOLD ALL PACKAGE DIMENSIONS AND BATTERY LIMITS.
- HOLD FLARE THERMAL RADIATION ZONES.



FOR INFORMATION- NOT TO BE USED FOR CONSTRUCTION

PERDAMAN PROJECT DESTINY
2.05 MTPA GRANULAR UREA PLANT
OVERALL PLOT PLAN
SITE 'C' AND SITE 'F'

DRAWING NUMBER: 140436-0000-46D1-0001 REV 00

Z593-88733	STAMICARBON 3100 MTPD UREA MELT/GRANULATION PLANT				00	14/03/19	ISSUED FOR ESTIMATION	RJ	CEC	BR	
9002-8273	SCC-800 2x1 OUTDOOR POWER PLANT LAYOUT				B1	14/02/19	ISSUED FOR CLIENT REVIEW	RJ	CEC	BR	
S-08508-M71001	HALDOR-TOPSOE GAS-BASED 3,507 MTPD AMMONIA PLOT PLAN				A2	08/02/19	ISSUED FOR INTERNAL REVIEW	RJ	CEC	BR	
140436-0000-41DD-0001	PRELIMINARY GRADING- PLAN AND SECTIONS				A1	01/02/19	ISSUED FOR INTERNAL REVIEW	RJ	CEC	BR	
DOCUMENT NUMBER	REFERENCE DOCUMENTS	DOCUMENT NUMBER	REFERENCE DOCUMENTS	REV	DATE	REVISION DESCRIPTION	DRN	CHK	DOA	DISL	EM



DESIGNED	C. CLOGHESHY	08/02/19
DRAWN	R. JOKI	08/02/19
CHECKED	C. CLOGHESHY	08/02/19
APPROVED	B. RANKIN	08/02/19
ENGINEERING MANAGER	DISC. LEAD	
ENGR. MGR.		
SCALE	1:2500	A0